### **PCT**

# WORLD INTELLECTUAL PROPERTY ORGANIZATION International Bureau



# INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification <sup>5</sup>:

B01D 45/14

A1

(11) International Publication Number: WO 94/23823

(43) International Publication Date: 27 October 1994 (27.10.94)

(21) International Application Number:

PCT/NL94/00079

(22) International Filing Date:

15 April 1994 (15.04.94)

(30) Priority Data:

3

9300651

16 April 1993 (16.04.93)

NL

(71) Applicant (for all designated States except US): ROMICO HOLD A.V.V. [NL/NL]; P.O. Box 810, Curação (AN).

(72) Inventor; and

- (75) Inventor/Applicant (for US only): BROUWERS, Jozef, Johannes, Hubertus [NL/NL]; Vaarwerkhorst 37, NL-7531 HK Enschede (NL).
- (74) Agent: PRINS, Hendrik, Willem; Arnold & Siedsma, Sweelinckplein 1, NL-2517 GK The Hague (NL).

(81) Designated States: AT, AU, BB, BG, BR, BY, CA, CH, CN, CZ, DE, DK, ES, FI, GB, HU, JP, KP, KR, KZ, LK, LU, LV, MG, MN, MW, NL, NO, NZ, PL, PT, RO, RU, SD, SE, SK, UA, US, UZ, VN, European patent (AT, BE, CH, DE, DK, ES, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, ML, MR, NE, SN, TD, TG).


**Published** 

With international search report.

(54) Title: ROTATING PARTICLE SEPARATOR WITH NON-PARALLEL SEPARATING DUCTS, AND A SEPARATING UNIT

### (57) Abstract

The invention relates to a separating body which can be set into rotation to separate solid or liquid particles of micron or sub-micron size from a fluid, wherein said body consists of a large number of separating ducts with singly connected walls over a substantial part of the axial length, characterized in that walls of at least one of the separating ducts are not parallel to the axis of rotation and that the tangent of the angle between the tangent planes of the walls of the separating duct and the axis of rotation designated with tan  $\alpha$ , the radial width of the separating duct designated with d, the length of the separating duct designated with L and the rotation speed of the separating body designated with  $\Omega$  are chosen in mutual dependence in a manner such that the dimensionless number ( $\Omega$  Ld tan  $\alpha$ )/v is located over a substantial part of the separating duct in the range up to 192, wherein v is the kinematic viscosity of the fluid. The inventio further relates to a separating unit provided with at least two separating bodies.



### FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AU Australia GE Georgia MW Malawi BB Barbados GN Guinea NE Niger BE Belgium GR Greece NL Netherlands BF Burkina Faso HU Hungary NO Norway BG Bulgaria IE Ireland NZ New Zealand BJ Benin IT Italy PL Poland BR Brazil JP Japan PT Portugal BY Belarus KE Ketrya RO Romania CA Canada KG Kyrgystan RU Russiam Federation CF Central African Republic KP Democratic People's Republic SD Sudan CG Congo of Korea SE Sweden CH Switzerland KR Republic of Korea SI Slovenia CI Côte d'Ivoire KZ Kazakhstan SK Slovakia CM Cameroon LI Liechterustein SN Senegal CN China LK Sri Lanka TD Chad CS Czechoslovakia LU Luxembourg TG Togo CZ Czect Republic MC Mouaco TT Tinidad and Tobago DK Demmark MD Republic of Moldova UA Ukraine	ΑT	Austria	GB	United Kingdom	MR	Mauritania
BB Barbados GN Guinea NE Niger BE Belgium GR GR Greece NL Netherlands BF Burkina Faso HU Hungary NO Norway BG Bulgaria IE Ireland NZ New Zealand BJ Benin IT Italy PL Poland BR Brazil JP Japan PT Portugal BY Belarus KE Ketya RO Romania CA Canada KG Kyrgystan RU Russian Federation CF Central African Republic KP Democratic People's Republic SD Sudan . CG Congo of Korea SE Sweden CH Switzerland KR Republic of Korea SI Slovenia CI Côte d'Ivoire KZ Kazakhstan SK Slovakia CM Cameroon LI Liectnenstein SN Senegal CN China LK Sri Lanka TD Chad CS Czechoslovakia LU Luxembourg TG Togo CZ Czech Republic LV Latvia TJ Tajikistan DE Germany MC Mouaco TT Trinidad and Tobago DK Deumark MD Republic of Moldova UA Ukraine ES Spain MG Madagascar US United States of Ame FF Finland ML Mali UZ Uzbekistan FF France				<u> </u>	MW	Malawi
BE Belgium GR Greece NL Netherlands BF Burkina Faso HU Hungary NO Norway BG Bulgaria IE Ireland NZ New Zealand BJ Benin IT Italy PL Poland BR Brazil JP Japan PT Portugal BY Belarus KE Ketya RO Romania CA Canada KG Kyrgystan RU Russian Federation CF Central African Republic KP Democratic People's Republic SD Sudan . CF Congo to Korea SE Sweden CH Switzerland KR Republic of Korea SI Slovenia CI Côte d'Ivoire KZ Kazakhstan SK Slovakia CM Cameroon LI Liectnessein SN Senegal CN China LK Sri Lanka TD Chad CS Czechoslovakia LU Luntembourg TG Togo CZ Czech Republic LV Latvia TJ Tajikistan DE Germany MC Mouaco TT Trindad and Tobago DK Denmark MD Republic of Moldova UA Ukraine ES Spain MG Madagascar US United States of Ame FF Finland ML Maii UZ Uzbekistan FF France			_	•	NE	Niger
BF Burkina Faso HU Hungary NO Norway BG Bulgaria IE Ireland NZ New Zealand BJ Benin IT Italy PL Poland BR Brazil JP Japan PT Portugal BY Belarus KE Kettya RO Romania CA Canada KG Kyrgystan RU Russian Federation CF Central African Republic KP Democratic People's Republic SD Sudan CG Congo TKorea SE Sweden CH Switzerland KR Republic of Korea SI Slovenia CI CAte d'Ivoire KZ Kazakhstan SK Slovakia CM Cameroon LI Liecthenstein SN Senegal CN China LK Sri Lanka ID Chad CS Czechoslovakia LU Luxembourg TG Togo CZ Czech Republic LV Latvia TJ Tajikistan DE Germany MC Monaco TT Trinidad and Tobago DK Demmark MD Republic of Moldova UA Ukraine ES Spain MG Madagascar US United States of Ame FI Finland ML Mali UZ Uzbekistan FI Finland ML Mali UZ Uzbekistan FI Finland ML Mali UZ Uzbekistan					NL	Netherlands
BG Bulgaria IE Ireland NZ New Zealand BJ Benin IT Italy PL Poland BR Brazil JP Japan PT Portugal BY Belarus KE Ketya RO Romania CA Canada KG Kyrgystan RU Russian Federation CF Central African Republic KP Democratic People's Republic SD Sudan CG Congo of Korea SE Sweden CH Switzerland KR Republic of Korea SI Slovenia CI Ckt d'Ivoire KZ Kazakhstan SK Slovakia CM Cameroon LI Liechtenstein SN Senegal CN China LK Sri Lanka ID Chad CS Czechoslovakia LU Lutembourg TG Togo CZ Czech Republic LV Latvia TJ Tajikistan DE Germany MC Mouaco TT Trinidad and Tobago DK Demark MD Republic of Moldova UA Ukraine ES Spain MG Madagascar US United States of Ame FF Finland ML Mali UZ Uzbekistan FF France					NO	Norway
BJ Benin IT Italy PL Poland BR Brazil JP Japan PT Portugal BY Belarus KE Kenya RO Romania CA Canada KG Kyrgystan RU Russian Federation CF Central African Republic KP Democratic People's Republic SD Sudan . CG Congo of Korea SE Sweden CH Switzerland KR Republic of Korea SI Slovenia CI Côte d'Ivoire KZ Kazakhstan SK Slovakia CM Cameroon LI Liechtenstein SN Senegal CN China LK Sri Lanka ID Chad CS Czechoslovakia LU Luxembourg IG Togo CZ Czech Republic LV Latvia IJ Tajikistan DE Germany MC Mouaco IT Trinidad and Tobago DK Demark MD Republic of Moldova UA Ukraine ES Spain MG Madagascar US United States of Ame FI Finland ML Mali UZ Uzbekistan FF France MN Mongolia					NZ	New Zealand
BR Brazil JP Japan PT Portugal BY Belarus KE Kettya RO Romania CA Canada KG Kyrgystan RU Russim Federation CF Central African Republic KP Democratic People's Republic SD Sudan . CG Congo of Korea SE Sweden CH Switzerland KR Republic of Korea SI Slovenia CI Côte d'Ivoire KZ Kazakhstan SK Slovakia CI Côte d'Ivoire KZ Kazakhstan SK Slovakia CM Cameroon LI Liectnenstein SN Senegal CN China LK Sri Lanka TD Chad CS Czechoslovakia LU Luxembourg TG Togo CZ Czech Republic LV Latvia TJ Tajikistan DE Germany MC Monaco TT Trinidad and Tobago DK Denmark MD Republic of Moldova UA Ukraine ES Spain MG Madagascar US United States of Ame FI Finland ML Mali UZ Uzbekistan FR France MN Mongolia					PL.	Poland
BY Belarus KE Kenya RO Romania CA Canada KG Kyrgystan RU Russian Federation CF Central African Republic KP Democratic People's Republic SD Sudan . CG Congo Se Grand SE Sweden CH Switzerland KR Republic of Korea SI Slovenia CI Côte d'Ivoire KZ Kazakhstan SK Slovakia CM Cameroon LI Liechteustein SN Senegal CN China LK Sri Lanka TD Chad CS Czechoslovakia LU Luxembourg TG Togo CZ Czech Republic LV Latvia TJ Tajikistan DE Germany MC Monaco TT Trinidad and Tobago DK Denmark MD Republic of Moldova UA Ukraine ES Spain MG Madagascar US United States of Ame FI Finland ML Mali UZ Uzbekistan FR France MN Mongolia VN Viet Nam	_	<del>-</del> · ·		· · · · · ·		
CA Canada KG Kyrgystan RU Russian Federation CF Central African Republic KP Democratic People's Republic SD Sudan CG Congo of Korea SE Sweden CH Switzerland KR Republic of Korea SI Slovenia CI Côte d'Ivoire KZ Kazakhstan SK Slovakia CM Cameroon LI Liechtenstein SN Senegal CN China LK Sri Lanka TD Chad CS Czechoslovakia LU Luxembourg TG Togo CZ Czech Republic LV Latvia TJ Tajikistan DE Germany MC Mouaco TT Trinidad and Tobago DK Demark MD Republic of Moldova UA Ukraine ES Spain MG Madagascar US United States of Ame FI Finland ML Mali UZ Uzbekistan FR France MN Mongolia VN Viet Nam			_	•		~
CA Canada  CF Central African Republic  CF Central African Republic  CG Congo  Of Korea  SE Sweden  CH Switzerland  KR Republic of Korea  SI Slovenia  CI Côte d'Ivoire  KZ Kazakhstan  SK Slovakia  CM Cameroon  LI Liechtenstein  SN Senegal  CN China  LK Sri Lanka  TD Chad  CS Czechoslovakia  LU Luxembourg  TG Togo  CZ Czech Republic  LV Latvia  TJ Tajikistan  DE Germany  MC Mouaco  TT Trinidad and Tobago  DK Deumark  MD Republic of Moldova  UA Ukraine  ES Spain  MG Madagascar  MI Mali  WZ Uzbekistan  FF France  MN Mongolia  VN Viet Nam	BY	Belarus		•	_	
CG Congo of Korea SE Sweden  CH Switzerland KR Republic of Korea SI Slovenia  CI Côte d'Ivoire KZ Kazakhstan SK Slovakia  CM Cameroon LI Liectnenstein SN Senegal  CN China LK Sri Lanka TD Chad  CS Czechoslovakia LU Luxembourg TG Togo  CZ Czech Republic LV Latvia TJ Tajikistan  DE Germany MC Mouaco TT Trinidad and Tobago  DK Deumark MD Republic of Moldova UA Ukraine  ES Spain MG Madagascar US United States of Ame  FI Finland ML Mali UZ Uzbekistan  FR France MN Mongolia VN Viet Nam	CA	Canada		·		
CH Congo CH Switzerland KR Republic of Korea SI Slovenia CI Côte d'Ivoire KZ Kazakhstan SK Slovakia CM Cameroon LI Liechtenstein SN Senegal CN China LK Sri Lanka TD Chad CS Czechoslovakia LU Luxembourg TG Togo CZ Czech Republic LV Latvia TJ Tajikistan DE Germany MC Mouaco TT Trinidad and Tobago DK Deumark MD Republic of Moldova UA Ukraine ES Spain MG Madagascar US United States of Ame FI Finland ML Mali UZ Uzbekistan FR France MN Mongolia VN Viet Nam	CF	Central African Republic	KP	• •		
CI Côte d'Ivoire KZ Kazakhstan SK Slovakia  CI Côte d'Ivoire KZ Kazakhstan SK Slovakia  CM Cameroon LI Liechtenstein SN Senegal  CN China LK Sri Lanka TD Chad  CS Czechoslovakia LU Lintembourg TG Togo  CZ Czech Republic LV Latvia TJ Tajikistan  DE Germany MC Monaco TT Trinidad and Tobago  DK Denmark MD Republic of Moldova UA Ukraine  ES Spain MG Madagascar US United States of Ame  FI Finland ML Mali UZ Uzbekistan  FR France MN Mongolia VN Viet Nam	CG	Congo		of Korea		
CI Côte d'Ivoire KZ Kazakhstan SK Slovária  CM Cameroon LI Liectienstein SN Senegal  CN China LK Sri Lanka TD Chad  CS Czechoslovákia LU Luxembourg TG Togo  CZ Czech Republic LV Latvia TJ Tajikistan  DE Germany MC Mouaco TT Trinidad and Tobago  DK Denmark MD Republic of Moldova UA Ukraine  ES Spain MG Madagascar US United States of Ame  FI Finland ML Mali UZ Uzbekistan  FR France MN Mongolia VN Viet Nam	CH	Switzerland	KR	Republic of Korea		•
CM Cameroon LI Liechtenstein SN Senegal CN China LK Sri Lanka TD Chad CS Czechoslovakia LU Luxembourg TG Togo CZ Czech Republic LV Latvia TJ Tajikistan DE Germany MC Monaco TT Trinidad and Tobago DK Demmark MD Republic of Moldova UA Ukraine ES Spain MG Madagascar US United States of Ame FI Finland ML Mali UZ Uzbekistan FR France MN Mongolia VN Viet Nam	-	Côte d'Ivoire	KZ	Kazakhstan		Slovakia
CN China LK Sri Lanka TD Chad  CS Czechoslovakia LU Lutembourg TG Togo  CZ Czech Republic LV Latvia TJ Tajikistan  DE Germany MC Mouaco TT Trinidad and Tobago  DK Deumark MD Republic of Moldova UA Ukraine  ES Spain MG Madagascar US United States of Ame  FI Finland ML Mali UZ Uzbekistan  FR France MN Mongolia VN Viet Nam			LI	Liechtenstein	SN	Senegal
CS Czechoslovakia LU Luxembourg TG Togo CZ Czech Republic LV Latvia TJ Tajikistan DE Germany MC Mouaco TT Trinidad and Tobago DK Desmark MD Republic of Moldova UA Ukraine ES Spain MG Madagascar US United States of Ame FI Finland ML Mali UZ Uzbekistan FR France MN Mongolia VN Viet Nam			LK	Sri Lanka	TD	Chad
CZ Czech Republic LV Latvia TJ Tajikistan  DE Germany MC Mouaco TT Trinidad and Tobago  DK Denmark MD Republic of Moldova UA Ukraine  ES Spain MG Madagascar US United States of Ame  FI Finland ML Maii UZ Uzbekistan  FR France MN Mongolia VN Viet Nam				Luxembourg	TG	Togo
DE Germany MC Mouaco TT Trinidad and Tobago DK Demmark MD Republic of Moldova UA Ukraine ES Spain MG Madagascar US United States of Ame FI Finland ML Mali UZ Uzbekistan FR France MN Mongolia VN Viet Nam			-	_	TJ	Tajikistan
DK Denmark MD Republic of Moldova UA Ucraine  BS Spain MG Madagascar US United States of Ame  FI Finland ML Mali UZ Uzbekistan  FR France MN Mongolia VN Viet Nam		-			TT	Trinidad and Tobago
ES Spain MG Madagascar US United States of Ame FI Finland ML Mali UZ Uzbekistan FR France MN Mongolia VN Viet Nam		•			UA	Ukraine
FI Finland ML Mali UZ Uzbekistan FR Prance MN Mongolia VN Viet Nam					US	United States of America
FR Prance MN Mongolia VN Viet Nam		•		<del>-</del>		Uzbekistan
kK turice					-	
GA Gabon			MIN	Workons	7.1	
	GA	Gabon				

# ROTATING PARTICLE SEPARATOR WITH NON-PARALLEL SEPARATING DUCTS, AND A SEPARATING UNIT

The invention relates to a separating body which can be set into rotation for the purpose of separating solid or liquid particles of micron or sub-micron size from a fluid, wherein the relevant body consists of a large number of separating ducts with singly connected walls over a substantial part of the axial length. The invention also relates to a rotating particle separator which consists of the above described separating body, onto which impellers may or may not be fixed upstream and downstream and wherein the separating body is mounted in a housing which is provided with a fluid inlet and fluid outlet, optionally with a separate outlet for removing separated particle material.

When a fluid is set into rotation liquid or solid particles found in the relevant fluid will displace in radial 15 direction, wherein the distance of the particles from the axis of rotation increases. The velocity with which the particles are displaced in radial direction depends on the magnitude of the centrifugal force acting on the particle as a result of the rotation and the resistant force the fluid 20 exerts on a particle making a movement relative to the fluid. On the basis of these forces it can be calculated that in the case of a gas rotating at an angular speed of 300 rad/s a particle with an average diameter of 1 micron, an average specific mass of about 1000 kg/m³ and situated on a radius of 25 0.1 m, displaces radially at a speed of about 0.03 m/s. Particles with average diameters of about 5 micron and about 0.05 micron will as a result of rotation generally be displaced radially under practically realistic conditions at respective speeds of about 0.1 m/s and about 0.001 m/s. If we 30 assume that gas and particles remain in rotation for a residence time of about 0.2 s, this then implies that the said particles will arrive at a radially placed wall if the said wall is situated at a radial distance which is respectively about 20 mm and about 0.2 mm removed from the

radial plane where the particles start their displacement. The use of a large number of walls placed at a short radial distance from each other and extending axially along the axis of rotation results in a configuration with which large amounts of gas can be purified of extremely small particles by means of centrifugal separation. The gas moves parallel to the radially placed walls and the axis of rotation, while the particles displace radially as a result of centrifugal action and are deposited on the outer walls of the separating ducts 10 which are formed by the radially placed walls. Similar considerations also apply for a liquid fluid.

The above specified particle separator is known from the European patent specification 0286160 and the American patent specifications 4,994,097 and 5,073,177. A drawback of 15 the known particle separator is that the separating ducts are parallel to the axis of rotation. The present invention is based on the new insight that within defined limits the separating ducts are placed non-parallel to the axis of rotation, which positively enhances the separating process.

Fluid which rotates and flows in a direction not parallel to the axis of rotation undergoes Coriolis forces. As a result convective flows occur in a plane perpendicular to the axis of rotation. Such convective flows can enhance the transport, primarily caused by centrifugal forces, of 25 particles to the wall of a separating duct. Already at very small inclination of the separating ducts in relation to the axis of rotation, for instance when the tangent planes to the walls of these ducts form an angle of only a hundredth of a degree of arc relative to the axis of rotation, convective 30 particle transport to the separating wall will make a noticeably positive contribution to the separating process.

Drawn in Fig. 1 by way of illustration is a section of the walls 1 of a separating duct in a plane containing the axis of rotation 2. The angles 3 which the walls form with the axis of rotation are indicated at various positions.

Drawn by way of illustration in Fig. 2 is a section of a circular separating duct 4 which forms part of a bundle of ducts according to the invention. When the walls of this duct are not parallel to the axis of rotation in the manner as

WO 94/23823 PCT/NL94/00079

shown for instance in Fig. 1, circulatory flows 5 will develop as a result of Coriolis forces. The flow pattern can consist of two cells as designated in Fig. 2, wherein the flow pattern is a consequence of the Coriolis force 6 which acts in a direction perpendicularly of the axis of rotation and perpendicularly of the axial velocity of the fluid through the duct. Due to the circulatory flow, particles are carried a shorter distance from the separating walls. The radial transport of particles resulting from centrifugal action is thus enhanced.

3

The degree of inclination of the separating ducts is however subject to limits. If the inclination is too large the convective fluid flows will begin to predominate as a result of Coriolis forces. In such a case particles will substantially follow the closed circulations of the fluid due to the Coriolis forces. The centrifugal force which acts on a particle and which is primarily responsible for moving a particle to a radially placed wall has in this case become too small. Particles will to a significant extent no longer reach the walls and be carried away with the fluid.

Of importance is the insight that the magnitude of these circulation flows must be limited to a value corresponding with the radial migration speed of the particles due to centrifugal action. This means that the angle a nonparallel duct forms with the axis of rotation, the rotation speed, the radial width and the length of the duct as well as the kinematic viscosity of the fluid that flows through the duct must be selected in mutual dependence in a manner such that a certain dimensionless number formed by these

The present invention therefore relates to a separating body which can be set into rotation to separate solid or liquid particles of micron or sub-micron size from a fluid, wherein the relevant body consists of a large number of separating ducts with singly connected walls over a substantial part of the axial length, characterized in that walls of at least one of the separating ducts are not parallel to the axis of rotation and that the tangent of the angle between the tangent planes of the walls of the

separating duct and the axis of rotation designated with tan  $\alpha$ , the radial width of the separating duct designated with d, the length of the separating duct designated with L and the rotation speed of the separating body designated with  $\Omega$  are chosen in mutual dependence in a manner such that the dimensionless number ( $\Omega$  Ld tan  $\alpha$ )/ $\nu$  is located over a substantial part of the separating duct in the range up to 192, wherein  $\nu$  is the kinematic viscosity of the fluid.

In the separating body the number of separating ducts in radial direction is generally greater than 10, such as 15 to 1000, more preferably about 20 to 500. The number of non-parallel separating ducts is generally more than 20 to 30%, for instance more than 60% or 90%. In preference virtually all the separating ducts are non-parallel in the manner described.

For optimum enhancement of the separating process it is further recommended that the dimensionless number lies within the range 1-192, preferably 1-140 and more preferably 1-96.

In general the number lies below 192, more preferably below 140, and a lower limit is generally 0.1, for instance 1 to 5 or 2 to 10.

In preference the separating body is provided with a spray or spouting unit for removal from a separating duct of particles separated therein with spray or spouting medium through the duct, so that during operation or non-operation separated particulate material can be removed rapidly and efficiently via and from each separating duct.

The particle separator can optionally be provided with two or more separating units with separating ducts of

different diameters. A pre-separation of coarser particles can thus be performed, whereby blockage of the narrower separating ducts by coarser particles is avoided. Instead of an additional separating unit use can also be made of an extended rotor outer wall on which blown-back particles are collected during regeneration.

In the case the separating body is rotatably drivable with a motor or via a pulley which is fixed flexibly to a frame the axis of symmetry will, in the case of imbalance because the separating body is suspended on one side, follow

a path in the form of a conical plane, in which case the separating ducts can be parallel to the axis of symmetry but due to imbalance now incline at an angle  $\alpha$  relative to the axis of rotation.

If in further preference the separating body is provided with fluid inlet and/or fluid outlet means such that the centrifugal pressure increase is equal to or greater than the pressure fall over the separating body, short-circuit flows are avoided and sealing means can optionally be dispensed with.

The invention further relates to a separating unit provided with at least two separating bodies.

The invention also relates to a separating body which can be set into rotation to separate solid or liquid

15 particles of micron or sub-micron size from a fluid, wherein said body consists of a large number of separating ducts with singly connected walls over a substantial part of the axial length, which is characterized in that it is provided with a spray or spouting unit for removal from a separating duct of particles separated therein with spray or spouting medium through the duct.

The invention also relates to a separating body which can be set into rotation to separate solid or liquid particles of micron or sub-micron size from a fluid, wherein said body consists of a large number of separating ducts with singly connected walls over a substantial part of the axial length, which is characterized in that the separating body is rotatably drivable with a motor or pulley which is fixed flexibly to a frame.

The invention also relates to a separating body which can be set into rotation to separate solid or liquid particles of micron or sub-micron size from a fluid, wherein said body consists of a large number of separating ducts with singly connected walls over a substantial part of the axial length, which is characterized in that it is provided with fluid inlet and/or fluid outlet means such that the centrifugal pressure increase is equal to or greater than the pressure fall over the separating body.

30

In these latter embodiments, that one or more separating ducts are non-parallel is not an essential condition for achieving the effects of the invention. This implies that the dimensionless number is smaller than 192 without a condition for the lower limit thereof.

In one embodiment of the separating body according to the invention the separating ducts consist of corrugated material wrapped round a shaft or pipe. The material can consist of paper, cardboard, foil, metal, plastic or ceramic.

In a further embodiment of the separating body according to the invention the separating ducts are formed by ducts in a perforated or otherwise axially porous body.

In a further embodiment of the separating body according to the invention the separating ducts are formed by concentric cylinders, wherein the space between the cylinders is intersected by a tangential wall.

In yet another embodiment of the separating body according to the invention the hydraulic diameter of the separating ducts and the average through-flow speed of the fluid in the separating ducts are chosen in mutual dependence in a manner such that the Reynolds number is smaller than 2300, and preferably smaller than 2000, thereby ensuring a laminar flow in the separating duct.

Ducts which are not parallel to the axis of rotation can be produced by means of the fabrication and/or assembly process of the separating body according to the invention. A non-parallel position also results if the separating body has a certain degree of imbalance. Particularly when the separating body is spring-mounted in a housing, for example in a manner analogous to the construction of a spin-drier, the separating body will rotate due to imbalance on an axis forming an angle with the axis of symmetry of the separating body.

In practice the ratio of length to radial width of a separating duct of the separating body according to the invention is large, and in any case larger than 5. Consider now the case of a separating body which rotates at an angular speed of 75 rad/s and has flowing through it air with a kinematic viscosity of 1.5x10<sup>-5</sup>m<sup>2</sup>/s. At a duct length of 500 mm

35

and a radial width of 3 mm the angle of inclination of the separating ducts according to the invention must then be limited to 1.5 degrees of arc. At a duct length of 200 mm and a radial width of 0.5 mm the angle of inclination of the 5 separating ducts according to the invention must be limited to 21 degrees of arc.

Shown in Fig. 3 and Fig. 4 are schematic drawings of a longitudinal section and a cross section of a particle separator provided with a separating body with separating 10 ducts 7 according to the invention. Situated upstream and downstream of the separating ducts are fluid guiding means, for instance impellers 8 and 9, provided with blades 10 which may or may not be curved. Fluid guiding means and separating ducts are mounted on a shaft 11 which is driven by motor 12. The whole is enclosed in a housing 13 provided with a volute 14.

The gas 15 for cleaning enters the housing axially on the underside and is set into rotation by means of inlet impeller 8 and guided into the rotating separating ducts 7. 20 Due to centrifugal action in combination with circulatory flows resulting from a limited inclination of the ducts according to the invention, an inclination which is not explicitly indicated in Fig. 3 and Fig. 5, liquid particles and solid particles separate from the gas and deposit on the 25 outer walls of the separating ducts. The gas with particles removed leaves the ducts via the outlet impeller 9 to leave the housing via volute 14. The particle material collected in the separating ducts can be removed by taking the separating body out of the housing and subsequently cleaning or 30 replacing it with a new body. The separating body can also be cleaned in situ, for instance by applying vibrations, by generating sound waves or, preferably, by spraying or spouting through the ducts with air or other gaseous or a liquid medium under pressure.

Possible leakage flows of cleaned gas at the outlet to the uncleaned gas at the entry or vice versa via the intermediate space between housing 13 and separating body 7 can be prevented by arranging seal 16. Such leakage flows can be likewise or further controlled by a suitably chosen

pressure distribution in the particle separator. As a consequence of centrifugal action gas flowing through impeller 8 and 9 in radial sense will undergo an increase in pressure. If this pressure increase is equal to the pressure 5 fall due to resistance the gas encounters when flowing through the separating ducts 7, the pressure at the outlet 14 will be the same as that in the entry 15 and no leakage flows will occur via the intermediate space. If the rotating particle separator is designed such that the centrifugal 10 pressure build-up of the gas is slightly greater than the pressure fall over the ducts, only a small back-flow of cleaned gas to uncleaned gas will take place. Special or high-grade seals 16 are not then necessary. Characteristic for such an embodiment is that the separating body and the 15 gas guiding means are constructed such that the cleaned gas exits at a radius which is greater than the radius at which the gas for cleaning enters.

An example of another possible embodiment of the rotating particle separator provided with a separating body according to the invention is shown in Fig. 5 and Fig. 6. Characteristic for this embodiment is a tangential inlet 17 which is placed upstream of the rotating separating body 18 which is provided with impeller 19 and is driven by motor 20. The gas for cleaning flows tangentially 21 into the cyclone-like inlet housing 17. As a result of centrifugal action due to the rotating movement of the gas in the inlet housing the coarser particles in the gas will be flung outward and leave the inlet housing via funnel 22. The finer particles will subsequently be separated in the separating ducts of the separating body. The gas with the particles removed leaves the rotating particle separator via impeller 19 and the volute outlet housing 23.

The particle material collected in the ducts can be removed periodically using a spray or spouting unit 24 which is horizontally displaceable over the ducts and which sprays or spouts air or another gaseous or a liquid medium through the ducts in upstream direction. Collected particle material is then moved to inlet housing 17 and leaves the rotating particle separator via funnel 22. This process can take place

both during standstill and during rotational operation. In the latter case the particle material blown out of the rotating separating body will be flung into the cyclone-like inlet housing 17 and, as in the pre-separation of coarser 5 particles, leave the inlet housing via funnel 22. By causing the blowing in upstream direction to take place in dosed and directed manner the separating process of the rotating particle separator is only disturbed to a small extent and regeneration of the rotating particle separator can take 10 place without it having to be rendered inoperative and the separating process interrupted.

Motor 20 is attached to the housing flexibly by means of springs and/or dampers 25. This achieves that imbalancing forces, which act on bearings and housing during rotation, 15 are minimal. The spring stiffness and/or damping force is chosen such that the angle  $\alpha$  between axis of rotation and walls of the separating ducts resulting from imbalance is in accordance with the characteristics of the separating body according to the invention.

The example of an embodiment of the rotating particle separator shown in Fig. 5 and Fig. 6 is particularly suitable for filtering gases from industrial processes with high concentrations of particle material, for instance gases from coal and waste burning plants, where concentrations of 10 to 100 gram/m³ are not unusual. A significant part of the 25 particle material often consists in such processes of coarser particles with diameters of about 10 micron and larger. This material is separated in the cyclone-like inlet space, whereby the concentration of particle material delivered to 30 the rotating separating body according to the invention becomes markedly lower, for instance 1 gram/m3. The time within which the ducts could become blocked can thereby be considerably extended, for example to more than an hour. Within this time compass the spray or spout unit 24, such as 35 an air jet, is set into operation in order to clear the separating body of particle material in good time and to allow the separating process to continue uninterrupted.

Concentrations of particle material in outside air are markedly lower than those usual in industrial process gases.

The concentrations of particle material in outside air are generally lower than 1 milligram/m³. When the rotating particle separator according to the invention is used for the purpose of air filtering the separating body will only become saturated after a long period of use which can amount to more than a year. In situ cleaning is then less necessary and the embodiment with axial inlet as shown in Fig. 3 and Fig. 4 is appropriate for such an application.

The rotating particle separator with non-parallel 10 separating ducts is suitable for separating both solid and liquid particles out of fluid. After being flung out into the separating ducts liquid particles will form a liquid film on the radial walls of the separating ducts. As a result of the force of gravity the liquid film will move downward in the 15 case of vertical placing of the walls of the separating ducts. The liquid leaves the ducts on the underside where, as a result of the centrifugal force, the liquid is thrown out in the form of droplets. These droplets can be drained by means of suitable provisions. For example, in the case of the 20 embodiment as shown in Fig. 5 and Fig. 6, the droplets will fall into the cyclone-like inlet space and leave the rotating particle separator via the funnel. In the case of the embodiment shown in Fig. 3 and Fig. 4, the droplets can leave the rotating particle separator through holes arranged in the 25 radial walls of the inlet impeller.

The liquid film occurring on the walls of the separating ducts in the case of liquid particle material will then only move downward when the liquid is subjected to a downward force. In the case the ducts are in inclining position a situation can occur wherein the downward oriented force of gravity is neutralized by the component of the centrifugal force which occurs in the lengthwise direction of the duct in the case of an inclining position. Such a situation can be prevented by limiting the inclination of the ducts to an angle whose tangent is smaller than the ratio of gravity and centrifugal force.

The rotating particle separator according to the invention can be a component of a chemical or physical process. Extremely fine particles can be dispersed in the

fluid at or prior to entry into the cyclone-like inlet
housing or by means of the spray unit 24 and can thus bring
about a chemical or physical conversion of the fluid or parts
of the fluid by absorption, desorption, adsorption, chemical

reaction or catalytic reaction. The fine particles are
separated in the rotating element. An effective rotating
reactor is thus created. The fact that operations can be
performed here with extremely small particles offers
interesting perspectives relative to existing reactors. The
comparatively large contact surface between the fluid phase
and the solid phase enables short reaction and capture times.
This results in a small reactor volume, or a compact
structure.

The rotating particle separator with non-parallel 15 separating ducts can also be used for separating condensable fluid-like components which are present in a fluid; for example, drying of air. Setting the fluid into rotation before entry into the separating ducts of the separating body according to the invention can take place such that cooling 20 occurs for instance due to expansion, and vapour-form components in the fluid condense to mist droplets. These droplets are separated in the separating ducts, whereafter the dried fluid leaves the rotating particle separator via the outlet impeller where the dried fluid is brought to the 25 desired pressure and temperature. Using the rotating particle separator a thermodynamic process is thus brought about wherein a fluid in vapour form is fractionated into a drier fluid and condensate of lower temperature. Such a process can be applied inter alia as alternative to existing energy 30 conversion systems including cooling systems based on freon, heating devices and heat pumps.

The rotating particle separator with non-parallel separating ducts according to the invention is also suitable for use in conditions wherein the fluid is under high pressure. In such applications the housing of the rotating particle separator can be constructed such that it is pressure-resistant, or the rotating particle separator as a whole can be placed in a separate pressure vessel. Possible sealing problems at the lead-through of the drive shaft of

the rotating particle separator can be solved by also displacing the drive inside the pressure vessel. In this manner very high pressures can be permitted up to 400 bar. High temperatures can also be permitted through suitable choice of material and by arranging cooling devices. With the use of high-grade metal alloys fluid temperatures of up to about 800°C can be permitted. If the internal components of the rotating particle separator according to the invention are made of ceramic, temperatures of up to 1600°C can be permitted.

The particle separators shown in Fig. 3, Fig. 4, Fig. 5 and Fig. 6 are only examples of possible embodiments of particle separators provided with separating body according to the invention. Subject to the type of application many other embodiments are possible. Characteristic herein is that the particle separators are provided with a separating body according to the invention, that impellers may or may not be arranged upstream and downstream of the separating body and that the separating body may or may not be placed in a housing provided with fluid inlet and fluid outlet and optionally a separate outlet for removing separated particle material.

In the filtering of large quantities of fluid there is the possibility of placing in parallel a plurality of 25 rotating particle separators according to the invention. The fluid flow for filtering is divided over the different rotating particle separators for subsequent collection, after filtering, in a collective discharge conduit. Since each rotating particle separator can be designed such that the 30 pressure in the fluid outlet is at least equal to the fluid pressure in the inlet, each rotating particle separator pumps its own fluid flow. If a rotating particle separator comes to a desired or undesired standstill in such an arrangement of rotating particle separators placed in parallel, the fluid 35 flow through the rotating particle separator that has come to a standstill will also stop. The arranging of valves in the feed and/or discharge conduits of the rotating particle separators, in order for instance to isolate a rotating particle separator that has come to a standstill from the other

operating rotating particle separators, is not necessary.

Scaling up to installations of large numbers of rotating particle separators according to the invention placed in parallel can thus take place in comparatively simple manner, wherein in order to reduce costs optional use can be made of a collective housing. This results in an installation whose filtering capacity is relatively unaffected by possible breakdown of a single unit.

The rotating particle separator according to the 10 invention offers the possibility of removing solid and liquid particles of micron and sub-micron size from small and large quantities of hot or cold fluid flows under high or low pressure in an exceptionally efficient and economic manner. Experiments performed with diverse prototypes exhibited 15 excellent and consistent separating performances with low energy consumption. Tests were performed with, among others, an apparatus with a cylindrical separating body with a diameter of 0.3 m and a length of 0.5 m provided with hexagonal separating ducts with a width of 3 mm. The body 20 rotated at an angular speed of 300 rad/s and flow rate therethrough was 1000 m³/hr. Extremely fine solid particles with diameters in the micron and sub-micron range were dispersed with concentrations of about 1  $g/m^3$  in the inlet air and subsequently separated in the ducts of the separating body. Using cascade impactors it was determined that all particles with an aerodynamic diameter of 1 micron and greater were separated for practically 100% in the separating body.

Separation efficiencies for particles with aerodynamic diameters of 0.1 micron to 1 micron varied between 85 and 100%. Saturation of the ducts occurred after feed of about 1 kg particle material. Total energy consumption, inclusive pressure loss and electrical energy consumption by the drive motor, amounted to about 1000 Pa expressed in power per unit of air flow.

The separating body of the test apparatus was spring mounted on the housing in analogy with the construction shown in Fig. 5. As a result of imbalance there occurred during rotation an angle of inclination between separating ducts and

25

axis of rotation of roughly 0.13 degrees of arc. This is in accordance with the characteristics of the separating body according to the invention, according to which in the present case a maximum angle of inclination of about 0.37 degrees of 5 arc is allowed. Experiments were also performed wherein the imbalance was deliberately increased such that the angle of inclination was greater than 0.37 degrees of arc. A marked decrease in the extent of separation of particle material was herein observed.

The experiments performed with the prototypes of the rotating particle separator according to the invention revealed excellent particle separative performance. Enchanced separative performance, in particular for particles in the sub-micron range, was due to electric forces. Electric fields 15 develop in the rotating body of the rotating particle separator, among others as the result of friction exerted between the rotating body and the fluid containing the particles. These fields support the migration process of the particles which more towards the collecting walls of the 20 separating ducts of the rotating particle separator. The beneficial effect of the electric fields can be further stimulated by loading the particles in the fluid by creating an electrostatic field, for example by applying differential voltage over plates or by inserting an ionizer.

The rotating particle separator with non-parallel separating ducts according to the invention offers the possibility of removing solid and liquid particles of micron and sub-micron size from small and large quantities of hot or cold fluid flows under high or low pressure in extremely 30 efficient and economic manner. It is an interesting alternative to existing filtering methods and also offers interesting perspectives for new fields of application where existing methods are not usable due to physical and/or economic limitations.

\*\*\*\*

30

#### **CLAIMS**

- 1. Separating body which can be set into rotation to separate solid or liquid particles of micron or sub-micron size from a fluid, wherein said body consists of a large number of separating ducts with singly connected walls over a 5 substantial part of the axial length, characterized in that walls of at least one of the separating ducts are not parallel to the axis of rotation and that the tangent of the angle between the tangent planes of the walls of the separating duct and the axis of rotation designated with tan 10  $\alpha$ , the radial width of the separating duct designated with d, the length of the separating duct designated with L and the rotation speed of the separating body designated with  $\boldsymbol{\Omega}$  are chosen in mutual dependence in a manner such that the dimensionless number ( $\Omega$  Ld tan  $\alpha$ )/ $\nu$  is located over a 15 substantial part of the separating duct in the range up to 192, wherein  $\upsilon$  is the kinematic viscosity of the fluid.
  - 2. Separating body as claimed in claim 1, wherein the dimensionless number lies within the range 1-192, preferably 1-140 and more preferably 1-96.
  - 3. Separating body as claimed in claim 1 or 2, provided with a spray or spouting unit for removal from a separating duct of particles separated therein with spray or spouting medium through the duct.
- 4. Separating body as claimed in claim 3, wherein the spray or spouting unit is displaceable over and positionable above each separating duct.
  - 5. Separating body as claimed in claims 1-4, wherein the separating body is rotatably drivable with a motor which is fixed flexibly to a frame.
  - 6. Separating body as claimed in claims 1-5, provided with fluid inlet and/or fluid outlet means such that the centrifugal pressure increase is equal to or greater than the pressure fall over the separating body.
  - 7. Separating body as claimed in claims 1-6, wherein the separating ducts are formed by corrugated material wrapped round a shaft or pipe.

PCT/NL94/00079

- 8. Separating body as claimed in claims 1-7, wherein the separating duct is formed by a perforated or porous body.
- 9. Separating body as claimed in claims 1-8, wherein the separating ducts are formed by concentric cylinders
  5 wherein the annulus is intersected by a tangential wall.
- 10. Separating body as claimed in claims 1-9, wherein the hydraulic diameter of the separating ducts and the average through-flow speed of the fluid in the separating ducts are chosen in mutual dependence in a manner such that the Reynolds number is smaller than 2300, and preferably smaller than 2000, whereby a laminar flow is obtained in the separating duct.
- 11. Separating body as claimed in claims 1-10, wherein the separating body is placed in a housing which is provided with a fluid inlet and a fluid outlet and optionally a particle outlet.
  - 12. Separating body as claimed in claim 11, wherein the housing comprises cyclone-like parts.
- 13. Separating body as claimed in claim 11 or 12,20 provided with means for allowing a chemical, physical and/or thermodynamic process to proceed.
  - 14. Separating body as claimed in any of the preceding claims, comprising means for electrically loading the particles to be separated.
- 25 15. Separating unit provided with at least two separating bodies as claimed in claims 1-14.

\*\*\*\*




FIG. 1







FIG. 2







### INTERNATIONAL SEARCH REPORT

International application No.

PCT/NL 94/00079 A. CLASSIFICATION OF SUBJECT MATTER IPC 5 B01D45/14 According to International Patent Classification (IPC) or to both national classification and IPC **B. FIELDS SEARCHED** Minimum documentation searched (classification system followed by classification symbols) IPC 5 B01D Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched Electronic data base consulted during the international search (name of data base and, where practical, search terms used) C. DOCUMENTS CONSIDERED TO BE RELEVANT Relevant to claim No. Citation of document, with indication, where appropriate, of the relevant passages Category \* 1,5-14 EP,A,O 532 105 (N.V. PHILIPS' A GLOEILAMPENFABRIEKEN) 17 March 1993 see the whole document 1,5-14 EP.A.O 286 160 (BB ROMICO B.V.) 12 October Α 1988 cited in the application see the whole document 1,9-12 GB, A, 604 927 (LINDEROTH) 7 October 1948 A see page 1, line 88 - page 3, line 26; figure 1 1,4 FR,A,1 202 388 (HEINRICH KOPPERS GESELLSCHAFT) 11 January 1960

4 - L	
X Further documents are listed in the continuation of box C.	Patent family members are listed in annex.
* Special categories of cited documents:  'A' document defining the general state of the art which is not considered to be of particular relevance  'E' earlier document but published on or after the international	"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention  "X" document of particular relevance; the claimed invention
filing date  1. document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)  O document referring to an oral disclosure, use, exhibition or other means  P document published prior to the international filing date but later than the priority date claimed	cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone  'Y' document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.  '&' document member of the same patent family
Date of the actual completion of the international search  3 August 1994	Date of mailing of the international search report  1 1. 08. 94
ı	1

Authorized officer

-/--

1

Fax: (+31-70) 340-3016

Name and mailing address of the ISA

see page 2; figures 1,2

European Patent Office, P.B. 5818 Patentlaan 2 NI, - 2280 HV Rijswijk Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,

Cubas Alcaraz, J

## INTERNATIONAL SEARCH REPORT

International application No. PCT/NL 94/00079

	TO SEE THE LITTLE SEE THE SEE THE SEE THE LITTLE SEE THE	PCI/NE 3	
C.(Continua Category	tion) DOCUMENTS CONSIDERED TO BE RELEVANT  Citation of document, with indication, where appropriate, of the relevant passages		Relevant to claim No.
A	GB,A,2 036 607 (BBC BROWN, BOVERI &		1,12
,	see page 1 - page 2; figures 1,2,5,6		1
4	DE,C,513 288 (FIRMA EDUARD THEISEN) 13 November 1930 see the whole document	·	1

1

## INTERNATIONAL SEARCH REPORT

Information on patent family members

International application No. PCT/NL 94/00079

Patent document cited in search report	Publication date	Patent family member(s)		Publication date	
EP-A-0532105	17-03-93	JP-A- US-A-	5200222 5221300	10-08-93 22-06-93	
EP-A-0286160	12-10-88	NL-A- JP-A- US-A- US-A-	8700698 1135516 4994097 5073177	17-10-88 29-05-89 19-02-91 17-12-91	
GB-A-604927		FR-A-	911261		
FR-A-1202388		DE-B- GB-A-	1099500 859097		
GB-A-2036607	02-07-80	CH-A- AU-B- AU-A- CA-A- DE-A- FR-A,B JP-C- JP-A- JP-B- NL-A- SE-B- SE-A- US-A-	633454 526418 5335579 1132919 2854140 2442664 1499965 55075718 63048565 7908670 430655 7909821 4285707	15-12-82 06-01-83 05-06-80 05-10-82 26-06-80 27-06-80 29-05-89 07-06-80 29-09-88 03-06-80 05-12-83 02-06-80 25-08-81	
DE-C-513288		NONE	. 4 2 4 4 5 5 5 6 7 7 7		